







Summary of	EN12976-2	SOLAR SYSTEM test results	Licence Number	ICIM-CLS-00178						
Annex to Solar KEYMARK Certificate			Issued	2023-11-20						
Company	ATI DI MARIANI SRL		Country	Italy						
Brand (optional)			Website	www.atimariani.it						
Street	Via E. Mattei, 461, Z.ind.4 Torre del Moro		E-mail	info@atimariani.it						
Postal Code	47522	Cesena (FC)	Tel. / Fax	+39 0547 609711						
System classification										
Application(s)	Hot water									
Solar loop, circulation principle	Other									
Direct solar loop / heat exchanger	Direct									
Open, vented or closed solar loop	Closed									
Drain back/down	Always filled (no drain)									
Store location	Outdoor									
Store orientation (of main axis)	Horizontal									
Type of auxiliary heating (internal back-up heat)	None									
If other auxiliary/internal back-up heating, please specify:										
Solar+supplementary OR Solar-only / Solar pre-heat	Solar only / Solar preheat									
Collector(s)			Heat store(s)							
Company	ATI DI MARIANI SRL		Company	ATI DI MARIANI SRL						
<i>Keymark lic.no. if available</i>	--		<i>Keymark lic.no. if available</i>	--						
Collector name	Per module			Store name	Total nominal volume	Gross height	Gross width	Gross depth	Auxiliary heated	Electrical aux. heating power
	Gross Area (Ag)	Gross length	Gross width							
HYDROSOL 200	1,89	951	1890	HYDROSOL 200	193	262	951	1890	--	--
Solar loop controller			Solar loop fluid							
<i>Keymark lic.no. if available</i>	--		Recommended/required	No recommend./requirements						
Company	--		Company	--						
Name	--		Name	--						
Solar loop pump - power range	-- W	to -- W	Freezing point	--	°C					
System family overview										
Collector name	Number of collectors in each configuration for each store									
		Store name								
	HYDROSOL 200									
HYDROSOL 200	1									
Testing Laboratory	SPF Institute for Solar Technology									
Website	www.spf.ch									
Test report id. number	S285									
Date of test report	2023-10-31									
Comments of test lab	Integrated Storage Collector (ICS)									
					 INSTITUT FÜR SOLARTECHNIK 					

Summary of	EN12976-2	test results	Certification No.		ICIM-CLS-00178				
Annex to Solar KEYMARK Certificate			Issued		2023-11-20				
Company	ATI DI MARIANI SRL		Country	Italy					
Brand (optional)			Website	www.atimariani.it					
Street	Via E. Mattei, 461, Z.ind.4 Torre del Moro		E-mail	info@atimariani.it					
Postal Code	47522	Cesena (FC)	Tel. / Fax	+39 0547 609711					
Parameters for systems extrapolation (Annex D)									
	Collector of measured system				Storage tank of measured system				
	A_{ref} [m ²]	--		Volume [l]	193				
	η_0	--		A_{hx} [m ²]	--				
	a_1 [W/Km ²]	--		Piping					
	a_2 [W/Km ²]	--							
	IAM (50°)	--		$U_{loop,p}$	--				
System parameters									
Name of System Configuration	Tested/Extrapol	A_c^* [m ²]	u_c^* [W/Km ²]	U_s [W/K]	C_s [MJ/K]	S_c [-]	D_L [-]	f_{aux} [-]	
HYDROSOL 200	Tested	1,25	0,04	8,80	0,7475	0,00	0,22	--	
Testing Laboratory			SPF Institute for Solar Technology						
Website			www.spf.ch						
Test report id. number			S285						
Date of test report			2023-10-31						
Test method			ISO 9459-5 (DST)						
Comments of test lab			 INSTITUT FÜR SOLARTECHNIK 						
Integrated Storage Collector (ICS)									

Summary of	EN12976-2	test results	Certification No.	ICIM-CLS-00178											
Annex to Solar KEYMARK Certificate			Issued	2023-11-20											
Company	ATI DI MARIANI SRL		Country	Italy											
Brand (optional)			Website	www.atimariani.it											
Street	Via E. Mattei, 461, Z.ind.4 Torre del Moro		E-mail	info@atimariani.it											
Postal Code	47522	Cesena (FC)	Tel. / Fax	+39 0547 609711											
System family overview															
Collector name	For each storage and collector size, give number of collectors														
	HYDROSOL 200														
HYDROSOL 200	1														
Name of system configuration			HYDROSOL 200												
Collector name	HYDROSOL 200	No. Collectors	1							Storage name	HYDROSOL 200				
Calculated annual results for "solar-only / preheat system"															
Location	Qd,sh MJ/y	Daily drawoff 170 l				Daily drawoff 200 l				Daily drawoff 250 l					
		Qd,hw	QL	Qpar	fsol	Qd,hw	QL	Qpar	fsol	Qd,hw	QL	Qpar	fsol		
		MJ/y	MJ/y	MJ/y	%	MJ/y	MJ/y	MJ/y	%	MJ/y	MJ/y	MJ/y	%		
Stockholm SE	0	9492	3417	0	36	11164	3628	0	33	13939	3805	0	27		
WürzburgDE	0	9114	3655	0	40	10691	3870	36	0	13371	4092	0	31		
Davos CH	0	10281	4801	0	47	12110	5062	0	42	15137	5328	0	35		
Athens GR	0	7064	4761	0	67	8326	5245	0	63	10407	5776	0	56		
Perf. indicators for the table above															
Qd,sh	MJ/y	Not relevant for solar domestic hot water system													
Qd	MJ/y	Annual heat demand for domestic hot water													
QL	MJ/y	Annual heat energy delivered by the solar system													
Qpar	MJ/y	Annual parasitic energy: (electricity for pumps/controllers)													
$f_{sol} = Q_L / Q_d$	-	Solar fraction													
Ref. conditions	Stockholm SE		Würzburg DE		Davos CH		Athens GR								
	G	1.157	1.230	1.684	1.736										
	Ta,ave	7,5	9,0	3,2	18,5										
	Tc,ave	8,5	10,0	5,4	17,8										
	± ΔTc	6,4	3,0	0,8	7,4										
G	kWh/m ²	Annual irradiation South, 45°													
Ta,ave	°C	Annual average outdoor air temperature													
Tc,ave	°C	Annual average mains cold water temp.													
ΔTc	K	Seasonal variation of Tc													
Th	45 °C	Desired hot water temperature (mixing valve temperature).													
Max. operating press. - collector side			600	kPa	Max. operating press. - tank side			600	kPa						
Testing Laboratory			SPF Institute for Solar Technology												
Website			www.spf.ch												
Test report id. number			S285												
Date of test report			2023-10-31												
Test method			ISO 9459-5 (DST)												
Comments of test lab			Integrated Storage Collector (ICS)												
			 INSTITUT FÜR SOLARTECHNIK 												

All values are subject to some uncertainty; e.g. the uncertainty on system output is typically in the range of ± 5 % to ± 15 %

Version 4.5, 2017-10-24

Summary of	EN12976-2	test results	Certification No.	ICIM-CLS-00178
Annex to Solar KEYMARK Certificate			Issued	2023-11-20

Company	ATI DI MARIANI SRL		Country	Italy
Brand (optional)			Website	www.atimariani.it
Street	Via E. Mattei, 461, Z.ind.4 Torre del Moro		E-mail	info@atimariani.it
Postal Code	47522	Cesena (FC)	Tel. / Fax	+39 0547 609711

System family overview

Collector name	For each storage and collector size, give number of collectors									
	HYDROSOL 200									
HYDROSOL 200	1									

Annual performance parameters in the frame of the EU regulation CDR 811, 812 and 813 dated 2013

Name of system configuration			HYDROSOL 200		
Collector name	HYDROSOL 200	No. Collectors	1	Storage name	HYDROSOL 200

Annual performance parameters in the frame of the EU regulation CDR 811, 812 and 813 dated 2013

Load profile	M	L	XL	XXL	
Annual heat demand (kWh)	1523	2799	4427	5626	
Auxiliary heat contribution	Q _{nonsol}				section 5.9.3.6, see note 1
Average climate (kWh)	749	1741	3095	4225	Strasbourg
Cold climate (kWh)	958	2026	3449	4597	Helsinki
Hot climate (kWh)	397	1226	2479	3584	Athens
Q _{aux} (kWh)					section 5.9.3.4, see note 1
Comply to the load profile (Yes/No)					section 5.10.6, see note 1
η_{wh_nonsol} (%)					section 5.9.3.5, see note 1
Q _{elec} (kWh)					section 5.9.3.5, see note 1
Q _{fuel} (kWh)					section 5.9.3.5, see note 1
V ₄₀ , measured (l)					section 5.10.7, see note 1

Auxiliary thermostat setting	--	°C	Effective power of auxiliary heater	--	kW
-------------------------------------	----	----	--------------------------------------------	----	----

Note 1: Clause of EN 12976-2:2017

Testing Laboratory	SPF Institute for Solar Technology
Website	www.spf.ch
Test report id. number	S285
Date of test report	2023-10-31
Test method	ISO 9459-5 (DST)

Comments of test lab	 INSTITUT FÜR SOLARTECHNIK 
Integrated Storage Collector (ICS)	